Abstract of quantities for Nagavara Tank.

No.	Items of work	Quantity	Unit	Rate
	BUND.			
1	Jungle clearing	20	Grade	
2	Cutting grips	1,755	Cyd.	
3	Earthwork to bund including watering and tamping	15,182	,,	
4	Turfing	8,474	Syd.	
5	Rough stone revetment, new with jelly backing ...	620	Cyd.	
6	Removing and resetting old stone revetment with new jelly.	200	,,	
7	Removing and refixing grade stones with cutting and printing figures.	23	Each	
8	Providing new index stones	22	,,	
9	Providing gauge stone	1	,,	
10	Providing Registered No. stone	1	,,	
11	Providing B. M. stones	2	,,	
12	Earthwork cutting bund...	180	Cyd.	
13	Do refilling with watering and tamping	180	,,	
14	Do excavation foundation ...	14	,,	
15	Surki concreate for filling foundations ...	318	Cft.	
16	Burnt brick in surki mortar	708	,,	
17	Burnt stone slabs dressed and fixed	222	Sft.	
18	Cement pointing	97	Sqr.	
19	Surki plastering	6·24	,,	
20	Cutting orifice	4	Each	
21	Plugrod and locking arrangements	1	Item.	
	WASTE WEIR.			
22	Earthwork excavation	150	Cyd.	
23	Surki concrete	2,040	Cft.	
24	Burnt brick in surki mortar	3,060	,,	
25	Surki plastering.	27·58	Sqr.	
26	Removing and refixing the crest slabs ...	484	Sft.	
27	Bond slabs	110	Each	
28	Cement pointing	4·50	...	

R. W. SCALDWELL,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification dated 30th September—1st October 1927.

The attention of the public is hereby invited to the advertisement in page No. 834 of the *Mysore Gazette* dated 13th October 1927, calling for tenders for the work of restoring Hampanur Minor Tank Reg. No. 58 of Chitaldrug Taluk.

A. TANDONI RAO,
Executive Engineer.

KOLAR DIVISION.

Notice dated 14th October 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 14th November 1927, for Restoring Birmanaballi Minor Tank, Register No. 347, Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1928.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the from given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Birmanaballi Minor Tank, Kolar Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be written in figures as well as in words.

Items of work	Per	Rate	Quantity	Cost	Total
		Rs. a. p.		Rs.	
Bund R. L. 55·00 top width 4½'.—					
Earthwork watering and tamping ...	C.yds.		5545		
Turfing to bund ...	Sqr.		374		
Removing and resetting old stone work for revetment.	C.yd.		406		
New stone work ...	"		506		
Grade stone including zero stone ...	No.		21		
Index stone ...	"		21		
B. M. stones ...	"		2		
Register No. stone with survey details ...	"		1		
Cutting trenches and scraping grass ...	Grade		18		
Cutting trees and prickly pier ...	"		15		
Total to bund ...					
Constructing sluice at R. L. 46·00—					
Earthwork cut opening the bund and refilling the same with watering and tamping.	C.yd.		56		
Concrete in surki mortar ...	C.ft.		110		
Burnt brick in surki mortar ...	"		310		
Burnt stone slabs 4" to 6" thick ...	S.ft.		112		
Plastering with surki mortar ...	Sqr.		3·27		
Making holes in slab for plugs, road and orifice.	No.		3		
Cast iron pipe of 4" in diameter of 9" lengths.	R.ft.		27		
Plug and rod with locking arrangements ...	No.		1		
Total for sluice ...					

Item of work	Per	Rate	Quantity	Cost	Total
		Rs. a. p.		Rs.	
Constructing weir at 50·00 at right—					
Earthwork excavation ...	C.yd.	...	167		
Filling foundation with surki concrete ...	C.ft.	...	302		
Burnt brick in surky mortar ...	"	...	516		
Burnt stone slabs 4" to 6" thick ...	S.ft.	...	344		
Plastering ...	Sqrs.	..	7·80		
Constructing apron ...	C.yd.	...	93		
Joggle joints ...	No.	...	7		
Total for weir ...	...	...	...		
Total of bund, sluice, and weir contingencies.	...	..	...		
Grand total ...	...	...	...		

S. SRINIVASA AIYAR,
Executive Engineer.

MEDICAL DEPARTMENT.

MYSORE PUBLIC HEALTH DEPARTMENT.

VACCINE INSTITUTE.

Abstract Notification dated 22nd October 1927.

Sealed tenders for the supply of certain articles etc., required for twelve months from 1st January 1928 to 31st December 1928 (both days inclusive) will be received by the Superintendent Vaccine Institute Bangalore, at his office up to 11 A.M. on Thursday the 15th December 1927.

For details please see the *Mysore Gazette* dated 20th October 1927 pages 887 to 891 Part VI,

J. A. ISWARA MURTI,
Superintendent.

THE EPIDEMIC DISEASES HOSPITAL, WARDS FOR INCURABLE PATIENTS AND THE LEPER ASYLUM, BANGALORE CITY.

Abstract Notification dated 28th September 1927.

The attention of the public is invited to the detailed notification dated 28th September 1927, calling for tenders for the supply of diet and other articles to the above institutions during the calendar year 1928, published on pages 863 to 865, Part VI of the *Mysore Gazette* dated 13th October 1927.

S. VARADA IYENGAR,
Medical Officer, Incurable Wards &
Epidemic Diseases Hospital and Superintendent,
Leper Asylum, Bangalore.

CHITALDRUG DISTRICT LOCK-UP.

Notice dated 20th October 1927.

Notice is hereby given that sealed tenders in triplicate on half-sheet foolscap size paper will be received at the Office of the Chitaldrug District Lock-up, by the undersigned at 11 A.M., on Tuesday the 15th November 1927, for the supply of articles of diet, etc., required for the use of the said office from 1st January 1928 to 31st December 1928 (inclusive).

2. No tenders will be received after the date and hour above mentioned.

3. Tenders to be superscribed "Tender for the supply of provisions to the Chitaldrug District Lock-up.

4. No tender will be received unless accompanied by a deposit of Rs. 25 in cash or currency notes or treasury receipts.